
Rev. 12-1101 Page 1 of 1 Uncontrolled Document



Design

Permissible concentricity deviation of hollow taper shank to location hole 0.005 mm. Permissible axial runout deviation of hollow taper shank of contact face 0.003 mm.

Standard Specification

Anti-fatigue bolt and tightened driving dogs included.

Note

When screwing the FLEXIBORE modules together the coolant tube has to be removed. Other designs and sizes are available on request.

Available for HSK-A 40, 50, 63, 80, 100



